

ESTIMATE



Prepared For

Amanda Schilling
7799 Woodview Ct
Maineville , Ohio
(513) 324-6065

Crystal Clear Cleaning & Contracting

7561 Easy St. , Unit D
Mason, OH 45040
Phone: (513) 614-8080
Email: crystalclearcontracting@yahoo.com
Web: crystalclearcontractors.com

Estimate # 4137
Date 06/24/2026

Description	Rate	Quantity	Total
Kitchen Remodel DEMOLITION	\$0.00	1	\$0.00

Contractor shall provide all labor and equipment necessary to perform selective demolition of existing kitchen area and adjoining pantry/closet space as required for new layout. This includes removal of existing cabinetry, countertops, non-structural wall components as needed, and preparation of work area for new construction.

All debris shall be removed from the site and disposed of properly.

2. STRUCTURAL MODIFICATIONS

Contractor shall modify existing load-bearing wall(s) as required to create open-concept kitchen and dining layout. Work includes installation of engineered LVL beam(s), temporary support, framing modifications, fastening, and integration into existing structure.

All structural work is subject to field verification and may require engineering approval if conditions require.

3. FRAMING / PANTRY MODIFICATIONS

Contractor shall reframe or eliminate existing pantry/closet shelving area as required by new design. Work may include framing inside garage/pantry wall area, closing openings, and preparing surfaces for finish work. No shelving systems are included unless otherwise specified.

4. ELECTRICAL SCOPE

Contractor shall modify and upgrade electrical system in kitchen and dining areas to accommodate new layout. Work includes:

- * Relocation and installation of recessed can lighting
- * Installation and/or relocation of pendant lighting fixtures
- * Installation of new switch locations and circuits as required
- * Rewiring of affected circuits due to kitchen and dining room combination
- * Coordination of layout changes to meet applicable electrical code

Any required panel upgrades or service upgrades are not included unless specified in writing.

5. LIGHTING

Contractor shall install customer-selected lighting fixtures including recessed lighting and pendant lighting. Fixture supply is by owner unless otherwise agreed. All placement subject to final layout approval prior to installation.

6. ISLAND INSTALLATION

Contractor shall install and secure kitchen island in designated location. Work includes leveling, fastening, and coordination for electrical and/or plumbing rough-ins if applicable. Cabinetry and finish materials are owner-supplied unless otherwise noted.

7. DRYWALL / PATCH / FINISH REPAIRS

Contractor shall patch, repair, and prepare all disturbed surfaces resulting from structural, electrical, and framing work. This includes drywall installation, finishing, texture blending, and preparation for paint. Final paint is not included unless stated.

8. GENERAL CONDITIONS

- * All work will be performed in a professional and workmanlike manner.
- * Contractor is not responsible for hidden conditions discovered during demolition (including but not limited to wiring, plumbing, structural deficiencies, or code violations).
- * Any additional work outside this scope will require a written change order.
- * Schedule may adjust due to inspections, material delays, or unforeseen field conditions.

9. EXCLUSIONS (UNLESS ADDED BY CHANGE ORDER)

- * Cabinets, countertops, and appliances
- * Plumbing modifications beyond island rough-in
- * Electrical panel upgrades or service upgrades
- * Painting
- * Flooring replacement or repair outside disturbed areas

Includes all Labor
Includes all Material

*Client to handle all baseboard and any Trim

***This is the range to complete the scopes listed above \$45-55k Labor Only quote
***Materials vary depending on selections. Would love to have another conversation about materials to help zoom in on a cost.

Hardwood Flooring	\$13,970.12	1	\$13,970.12
Demo Carpet and Tile			

FLOORING INSTALLATION & DEMOLITION QUOTE

*Installation of Raw Wood and Stain

SCOPE OF WORK

1. DEMOLITION

Contractor shall provide all labor, equipment, and disposal for removal of existing floor coverings in the following areas:

- * Living Room #1 (13' x 26') – carpet removal and disposal
- * Living Room #2 (13' x 20') – carpet removal and disposal
- * Kitchen (20' x 15') – tile demolition and disposal
- * Hallways (7' x 3' and 13' x 7') – tile demolition and disposal
- * Bathroom (5' x 5') – tile demolition and disposal

All debris will be hauled off site and properly disposed of.

2. BATHROOM PLUMBING RESET

Contractor shall remove and reset existing toilet to allow for flooring installation. New wax ring and reconnection included. Any additional plumbing repairs or code upgrades are not included unless specified in writing.

3. SUBFLOOR PREPARATION

After demolition, contractor shall prepare all subfloors for hardwood installation. This includes

cleaning, minor leveling, fastening loose areas, and ensuring proper conditions for installation. Any major subfloor repair, rot, moisture damage, or structural correction will be handled via change order.

4. HARDWOOD FLOOR INSTALLATION

Contractor shall install hardwood flooring throughout all listed areas:

- * Living Room #1
- * Living Room #2
- * Kitchen
- * Hallways
- * Bathroom

Installation includes layout, cutting, fitting, and installation per manufacturer specifications and industry standards.

5. TRIM WORK (EXCLUDED)

Client is responsible for all baseboard and trim installation after flooring is complete. Contractor may remove existing trim where necessary to complete demolition and installation.

6. GENERAL CONDITIONS

- * Contractor is not responsible for hidden or unforeseen conditions including but not limited to subfloor damage, moisture issues, or previous improper installations.
- * Any additional work outside of this scope will require a written change order.
- * Flooring materials must be on site prior to installation unless otherwise agreed.
- * Schedule is subject to material availability and site conditions.

EXCLUSIONS

- * Baseboard / trim installation
- * Painting or drywall repair
- * Major subfloor replacement or structural repair
- * Furniture moving (unless added)

Includes Labor

Includes Material

Subtotal	\$13,970.12
Total	\$13,970.12

**If paying with a credit card, there will be a 3.5% fee added to the invoice after we are notified that this is your choice of Payment.

**Prices on material for future jobs may be subject to change depending on all new tariffs. If pricing is to change we will discuss prior to starting each project.

**Only Scope of Work on this Contract is being Completed. If any additional work is required or requested, additional fees will apply and added to a Change-Order or the Final Invoice.

**By you the Client Signing or E-Signing this Contract and agreeing to the terms of this scope listed makes this a Legal Binding Contract.

**If for any reason the Contract needs to be Voided, a one-time fee of \$250 is to be paid for Cancellation of this Contract.

**Final Payment is due on the day of Completion. Late Fees will apply.

Attached is our Business Insurance

cid:EE7E8421-8B0D-4AB2-A39F-1F00598EB71D

By signing this document, the customer agrees to the services and conditions outlined in this document.

Amanda Schilling