

# ESTIMATE



## Prepared For

Katie Reece  
5050 Hamilton Middletown Rd  
Hamilton , Ohio 45011  
(513) 502-0489

## Crystal Clear Cleaning & Contracting

7561 Easy St. , Unit D  
Mason, OH 45040  
Phone: (513) 614-8080  
Email: crystalclearcontracting@yahoo.com  
Web: crystalclearcontractors.com

Estimate # 4143  
Date 06/26/2026

| Description       | Rate    | Quantity | Total       |
|-------------------|---------|----------|-------------|
| curb Installation | \$77.00 | 800      | \$61,600.00 |

### CURB DEMOLITION & REPLACEMENT QUOTE

Project: Remove & Replace Concrete Curbing  
Quantity: 800 Linear Feet

### Scope of Work

- \* Sawcut and remove existing concrete curb
- \* Haul off and dispose of all demo material
- \* Grade and prep sub-base as needed
- \* Form and set new curb line
- \* Install new reinforced concrete curb (commercial grade mix)
- \* Finish, edge, and tool joints for proper drainage and durability
- \* Cleanup and site restoration

### Optional Notes / Adjustments

- \* If existing base is unstable or requires stone rework: +\$3-\$6/LF
- \* If DOT/spec curb or reinforced heavy highway curb is required: +\$5-\$12/LF
- \* If traffic control or lane closures are required: priced separately
- \* Weather delays or unknown underground utilities may affect schedule
- \*\*\*Not responsible for any damage to the anything on the backside of the curb

### TERMS & CONDITIONS

This proposal is based on visible conditions at time of inspection. Any hidden or unforeseen conditions including poor subgrade, buried debris, undocumented utilities, or additional base failure will require a written change order and additional cost.

Contractor is not responsible for underground utilities that are unmarked, mis-marked, or unknown. Call 811 will be completed where required, but accuracy of markings is not guaranteed.

Permit requirements, engineering, inspections, and traffic control (if required) are excluded unless specifically listed.

Schedule is weather dependent and may be adjusted due to rain, freezing conditions, material delays, or site access issues.

Concrete is a natural material and minor cracking, color variation, or surface shrinkage is considered normal and not a defect in workmanship.

All change orders must be approved in writing prior to additional work being performed.

Includes all Material  
Includes all Labor

---

|                 |                    |
|-----------------|--------------------|
| <b>Subtotal</b> | \$61,600.00        |
| <b>Total</b>    | <b>\$61,600.00</b> |

---

**\*\*If paying with a credit card, there will be a 3.5% fee added to the invoice after we are notified that this is your choice of Payment.**

**\*\*Prices on material for future jobs may be subject to change depending on all new tariffs. If pricing is to change we will discuss prior to starting each project.**

**\*\*Only Scope of Work on this Contract is being Completed. If any additional work is required or requested, additional fees will apply and added to a Change-Order or the Final Invoice.**

**\*\*By you the Client Signing or E-Signing this Contract and agreeing to the terms of this scope listed makes this a Legal Binding Contract.**

**\*\*If for any reason the Contract needs to be Voided, a one-time fee of \$250 is to be paid for Cancellation of this Contract.**

**\*\*Final Payment is due on the day of Completion. Late Fees will apply.**

Attached is our Business Insurance

cid:EE7E8421-8B0D-4AB2-A39F-1F00598EB71D

By signing this document, the customer agrees to the services and conditions outlined in this document.

---

Katie Reece