

ESTIMATE



Prepared For

Sean Jones
7136 Hearthwood
Fairfield , Ohio
(513) 503-5006

Crystal Clear Cleaning & Contracting

7561 Easy St. , Unit D
Mason, OH 45040
Phone: (513) 614-8080
Email: crystalclearcontracting@yahoo.com
Web: crystalclearcontractors.com

Estimate # 4169
Date 07/13/2026

Description	Rate	Quantity	Total
Concrete	\$13,781.12	1	\$13,781.12

Scope of Work

Contractor shall furnish all labor, materials, equipment, and supervision necessary to complete the following work:

Concrete Pad

- Form and pour one 42' × 16' concrete pad (672 sq. ft.) 10 x10 section 7" deep for hot tub

-Every 5' dig a footer 12" wide X 33" deep to help support pad

- 4" thick, 4,000 PSI fiber-reinforced concrete
- Install one 12" turned-down edge along the 42-foot side
- Install and compact approximately 4" of #57 limestone gravel base
- Install #4 rebar on a 2' × 2' grid/Concrete mix will include fiber mesh
- Finish with a broom finish
- Saw-cut control joints
- Strip forms and clean job site

Concrete Steps

- Form, reinforce, pour, and finish seven (7) concrete steps
- Steps approximately 5 feet wide with 18-inch treads
- Includes excavation, gravel base, rebar, forming, finishing, and cleanup

Proposal Includes

- All labor
- Concrete
- Gravel base

- ## Exclusions

This proposal is valid for 30 days from the date above.

Includes all Labor

Subtotal	\$13,781.12
Total	\$13,781.12

cid:EE7E8421-8B0D-4AB2-A39F-1F00598EB71D

By signing this document, the customer agrees to the services and conditions outlined in this document.

Sean Jones