

ESTIMATE



Prepared For

Brian Starr
2772 Minton
Hamilton , Ohio 45013
(513) 417-2886

Crystal Clear Cleaning & Contracting

7561 Easy St. , Unit D
Mason, OH 45040
Phone: (513) 614-8080
Email: crystalclearcontracting@yahoo.com
Web: crystalclearcontractors.com

Estimate # 4175
Date 07/15/2026

Description	Rate	Quantity	Total
Decorative Stamped Concrete Patio	\$13,652.40	1	\$13,652.40
Concrete Demolition & Replacement			

Contractor shall demolish and remove the existing concrete porch and walkway, including all debris generated during demolition. The existing concrete areas include:

- * Front porch: approximately 15' × 17'
- * Walkway section: approximately 8' × 6'
- * Walkway section: approximately 3' × 44'

During demolition, Contractor shall also remove the two existing brick wing walls extending from the porch. Any required brick repair, reconstruction, or matching masonry beyond demolition is included in this scope

Following demolition, Contractor shall prepare the subgrade as needed and install a new reinforced concrete slab using a fiber-reinforced concrete mix and fiberglass rebar reinforcement for increased durability and crack resistance. Concrete shall be placed, finished, and cured in accordance with industry standards.

Stamped Concrete

The porch area (approximately 15' × 17') shall receive a wood plank stamped concrete finish. Final stamp pattern, integral color, release color, and sealer selection shall be determined by Owner prior to installation. Contractor shall apply a high-quality sealer upon completion after the concrete has cured appropriately.

Exclusions

The following items are specifically excluded from this contract unless otherwise noted in writing:

- * Landscaping restoration.
- * Topsoil, grading beyond normal concrete preparation, grass seed, straw, mulch, shrubs, or landscape repairs.
- * Any landscaping materials required to border or finish around the new concrete installation.
- * Repairs to irrigation systems, underground utilities, or drainage systems not visible prior to demolition.
- * Brick repair or reconstruction beyond demolition of the existing brick wing walls.
- * Any unforeseen conditions discovered during demolition requiring additional labor or materials.

Owner is responsible for coordinating any landscaping restoration with a landscape contractor following completion of the concrete work.

Change Orders

Any additional work requested by the Owner or required due to unforeseen site conditions shall be completed only upon written approval and may result in additional charges.

Disclaimers (Concrete)	\$0.00	1	\$0.00
General Contracting Disclaimers			

- * Contractor is not responsible for concealed conditions, underground utilities, unsuitable soils, or unforeseen site conditions discovered after demolition. Any additional work required will be treated as a change order.
- * Minor hairline shrinkage cracks, slight color variations, surface mottling, and normal curing characteristics are inherent to concrete and are not considered defects.
- * Final concrete color, stamped appearance, and texture may vary slightly from samples due to weather, curing conditions, and natural material variations.
- * Owner is responsible for keeping all foot and vehicle traffic off newly placed concrete for the recommended curing period as directed by Contractor.
- * Landscaping restoration, grading beyond the work area, grass, seed, straw, mulch, irrigation repairs, and other site restoration are excluded unless specifically stated in this agreement.
- * Contractor is not responsible for damage to unmarked or improperly located underground utilities, sprinkler systems, drain lines, or private utility lines.
- * Any work requested outside the original scope shall require a written change order and may result in additional charges.
- * Owner is responsible for obtaining any required HOA approvals prior to construction. Permit responsibility shall be as specified in this agreement.
- * Contractor warrants workmanship in accordance with industry standards. This warranty does not cover damage resulting from settlement, freeze/thaw cycles, deicing salts, excessive loads, improper maintenance, acts of nature, or misuse.
- * Payment is due according to the terms of this agreement. Delays in payment may result in work stoppage and additional costs.

Exterior Painting	\$10,530.00	1	\$10,530.00
Front of house - paint brick, soffits, gutter, fascia.			

Left of house - paint brick, soffit,
Fascia

Right side of house - paint brick, soffit, gutter, fascia, garage door and trim

Rear of house including rear of garage - paint brick, soffit, fascia

Total of 7 downspouts

Total of 4 doors and frames

All brick will be sprayed and back rolled with a coat of block filler and top coated with Sherwin Williams loxon.

All trim, soffits, gutter and downspouts will be coated with Sherwin Williams duration in a vinyl safe formula.

Includes Labor
Includes Material

	Subtotal	\$24,182.40
	Total	\$24,182.40

- **If paying with a credit card, there will be a 3.5% fee added to the invoice after we are notified that this is your choice of Payment.
- **Prices on material for future jobs may be subject to change depending on all new tariffs. If pricing is to change we will discuss prior to starting each project.
- **Only Scope of Work on this Contract is being Completed. If any additional work is required or requested, additional fees will apply and added to a Change-Order or the Final Invoice.
- **By you the Client Signing or E-Signing this Contract and agreeing to the terms of this scope listed makes this a Legal Binding Contract.
- **If for any reason the Contract needs to be Voided, a one-time fee of \$250 is to be paid for Cancellation of this Contract.
- **Final Payment is due on the day of Completion. Late Fees will apply.

Attached is our Business Insurance

cid:EE7E8421-8B0D-4AB2-A39F-1F00598EB71D

By signing this document, the customer agrees to the services and conditions outlined in this document.

Brian Starr