

ESTIMATE



Prepared For

Joey Wykoff
7014 Spruce Hill Circle
West Chester , Ohio 45069
(513) 470-5639

Crystal Clear Cleaning & Contracting

7561 Easy St. , Unit D
Mason, OH 45040
Phone: (513) 614-8080
Email: crystalclearcontracting@yahoo.com
Web: crystalclearcontractors.com

Estimate # 4244
Date 08/26/2026

Description	Rate	Quantity	Total
Master Bathroom Remodel	\$0.00	1	\$0.00

Bathroom Remodel

MASTER BATHROOM RENOVATION QUOTE

Project: Master Bathroom Renovation

SCOPE OF WORK

1. Demolition & Preparation

- Remove existing bathroom flooring as required to prepare for new tile installation.
- Remove existing water wall/partition wall in the shower area. TBD
- Remove damaged or deteriorated drywall in the bathroom, including affected corner areas and the existing damaged drywall section in the center of the room.
- Remove existing shower components as necessary for the planned shower renovation.
- Remove existing vanity top, mirror, vanity light, exhaust fan, and other items being replaced.
- Remove existing baseboard and trim as necessary for the renovation.
- Protect remaining areas of the home and maintain a reasonably clean work area throughout construction.
- Remove and dispose of demolition debris generated by the included scope of work.

2. Shower Wall Reconfiguration

- Demolish the existing water wall/partition.
- Reframe the affected wall area as necessary to create the new wall configuration.
- The goal will be to move the wall back to the existing/regular wall line where possible.
- Extend the shower area as discussed, provided there are no unforeseen plumbing, electrical,

structural, or other obstructions inside the existing wall.

- Final shower dimensions and extent of the shower extension will be determined after demolition and inspection of the existing conditions.
- No shower door is included at this time.

3. Plumbing

- Reroute existing water lines into the new wall framing as required following demolition and reframing.
- Plumbing will be relocated to accommodate the revised shower layout.
- Final plumbing scope is TBD after the existing wall is opened.
- Any additional plumbing required due to concealed conditions, damaged piping, unexpected obstacles, or changes to the agreed-upon layout will be addressed separately.
- Existing plumbing locations and conditions cannot be fully verified until the wall is opened.

4. Shower Waterproofing – Wedi System

- Install a Wedi waterproof shower system on the shower walls prior to tile installation.
- Prepare the shower walls and substrate for the Wedi system.
- Install Wedi waterproofing panels and associated system components in accordance with manufacturer requirements.
- Properly seal joints, penetrations, corners, and transitions as required.
- Prepare the completed waterproofing system to receive tile.

5. Shower Tile Installation

- Install tile on the shower walls over the Wedi waterproofing system.
- Install tile base at the shower perimeter as applicable.
- Install four corner shelves within the shower.
- No accent tile or decorative tile pattern is included at this time.
- A recessed shower niche may be added if selected by the homeowner. Niche pricing and scope to be determined separately.

6. Bathroom Floor Tile

- Prepare bathroom floor for new tile installation.
- Install new floor tile throughout the designated master bathroom floor area.
- Provide appropriate tile underlayment/preparation as required by existing conditions and selected flooring system.
- Install grout and finish tile installation.
- Install a new transition between the bathroom flooring and adjoining flooring as required.

7. Drywall Repairs & Finishing

- Patch and repair damaged drywall throughout the bathroom.
- Repair drywall at affected corners.
- Repair the existing damaged drywall section in the center of the room.
- Patch drywall areas affected by removal of the existing water wall.
- Install new drywall where required following demolition and reframing.
- Tape, mud, sand, and prepare repaired areas for primer and paint.

- Blend repaired areas as reasonably possible with the existing surrounding surfaces.

8. Vanity & Bathroom Accessories

- Install new vanity top.
- Install new mirror.
- Install new vanity light fixture.
- Install new bathroom exhaust fan.
- Install new shelf.
- Install toilet paper holder.
- Install towel bar/holder.
- Install designated bathroom accessories in agreed-upon locations.
- install new vanity.

9. Toilet

- Remove and reinstall the new toilet as necessary during flooring installation.
- Install toilet upon completion of the flooring work.
- Replace toilet seal as necessary during reinstallation.
- Connect to existing plumbing.

10. Baseboard & Trim

- Install new baseboard throughout renovated bathroom areas.
- Install/replace trim as required around affected areas.
- Caulk and prepare new trim for paint.

11. Painting

- Prepare bathroom walls, ceiling, and trim for painting.
- Prime repaired drywall areas as required.
- Paint bathroom walls.
- Paint ceiling.
- Paint baseboard and trim.
- Apply finish coats as necessary to achieve a consistent finished appearance.

ITEMS TO BE DETERMINED

The following items will be finalized after demolition and/or homeowner selection:

- Final amount of shower extension.
- Plumbing relocation requirements after the existing water wall is removed.
- Any concealed plumbing, electrical, structural, or framing conditions discovered during demolition.
- Addition of a recessed shower niche, if desired.
- Final tile selections and layout.
- Any additional work required due to unforeseen existing conditions.

EXCLUSIONS

- Shower door or enclosure.

- Accent/decorative tile.
- Shower niche unless specifically added to the scope.
- Major structural modifications.
- Repairs to concealed plumbing, electrical, framing, or subfloor damage not visible prior to demolition.
- Relocation of plumbing beyond what is required for the agreed-upon shower configuration.
- Any work not specifically described in this proposal.

PROJECT NOTES & DISCLAIMERS

1. Existing Conditions: The scope is based on currently visible conditions. Hidden conditions cannot be fully determined until demolition has been completed.
2. Plumbing: Plumbing relocation is contingent upon what is discovered inside the existing water wall. Any additional plumbing work beyond the anticipated relocation will be reviewed with the homeowner before proceeding.
3. Shower Configuration: The final shower size and configuration will be determined after the water wall is removed and the existing framing and plumbing are exposed.
4. Waterproofing: The shower will utilize the Wedi waterproofing system prior to tile installation. Waterproofing installation will be performed according to the manufacturer's installation requirements.
5. Tile: Tile is subject to normal variations in color, size, texture, and manufacturing. Final tile layout will be established prior to installation.
6. Existing Structure: Any structural, framing, subfloor, or other concealed damage discovered during demolition is not included unless specifically added to the scope of work.
7. Change Orders: Additional work outside the stated scope will require homeowner approval before the work is performed.
8. Paint & Finish: Existing surfaces may show differences in texture or appearance after repairs due to age and existing conditions. Reasonable efforts will be made to provide a uniform finished appearance.
9. Schedule: Project duration may be affected by material availability, concealed conditions, homeowner selections, and unforeseen repairs discovered during demolition.

Labor Only

****Behind the scene material will range from 3000-4000 roughly. Please remember this is just a good guestimate and is only an educated range.**

***Finish Material not priced in this quote**

Deck	\$46,671.23	1	\$46,671.23
------	-------------	---	-------------

Built out of pressure treated wood in the size of 17' x 27' with 1 set of steps that turn at 90 degrees in the center and land on Existing Paver Patio

Dig Footers at 20" Diameter x 30" Depth

Pour Cement Footers

Install Support Posts

Hang Ledger Board

Install Floor Joists

Install "Bump Out" Portion of Deck Near Stairs

Install Additional Blocking to Support "Picture Frame" Border

Install Stairs with Platform Landing in the Middle

Install Deck Boards
Install Picture Frame
Install Railing System
Install Fascia Covering On Exposed Framing

*Customer to cover permit costs
*If Customer Would Prefer Crystal Clear to Handle Permits, Additional Fees May Apply

This includes all labor
Includes all Material
Includes all Cleanup

16 x 24 new composite deck. *****

Bathroom Remodel	\$0.00	1	\$0.00
KIDS BATHROOM RENOVATION QUOTE			

Project: Kids Bathroom Tub-to-Shower Conversion and Full Bathroom Remodel

SCOPE OF WORK

1. Demolition & Preparation

- * Remove the existing bathtub and shower components.
- * Remove existing bathroom flooring as required to prepare for new tile installation.
- * Remove existing baseboard, trim, and other flooring-related materials as necessary.
- * Remove the existing vanity.
- * Remove the existing mirror and vanity light.
- * Remove the toilet as necessary to complete the flooring and remodeling work.
- * Remove the existing exhaust fan as required for replacement.
- * Remove and dispose of demolition debris generated by the included scope of work.
- * Protect adjacent areas of the home and maintain a reasonably clean work area throughout construction.
- * The existing walls and ceiling appear to be generally clean; drywall removal will be limited to areas affected by demolition, plumbing, framing, or other necessary work.

2. Tub-to-Shower Conversion

- * Remove the existing bathtub and prepare the area for a custom shower installation.
- * Inspect the existing shower and plumbing wall after demolition.
- * If necessary, construct a new water wall on the left-hand side of the shower area.
- * Relocate existing plumbing into the new water wall if required.
- * If the existing plumbing can remain in place, the shower will be configured around the existing plumbing locations.

- * Final shower dimensions will be based on the space remaining after demolition and any required plumbing or framing adjustments.
- * Install a custom Wedi shower pan sized to the final approved shower dimensions.
- * No shower door or enclosure is included unless added by written change order.

3. Plumbing

- * Disconnect and remove plumbing connections associated with the existing tub/shower as required.
- * Modify or relocate plumbing to accommodate the new shower configuration.
- * Construct a new water wall on the left-hand side if required by existing conditions.
- * Relocate shower valve, supply lines, and other plumbing components as necessary.
- * The need for a new water wall and the extent of plumbing relocation will be determined after the existing shower area is opened.
- * Any concealed plumbing damage, unexpected obstacles, or plumbing work beyond the anticipated conversion will be reviewed with the homeowner before proceeding.

4. Shower Waterproofing – Wedi System

- * Install a custom Wedi shower pan sized to the final shower opening.
- * Install Wedi waterproofing panels on the shower walls.
- * Seal all Wedi joints, corners, penetrations, transitions, and connections according to manufacturer requirements.
- * Prepare the completed waterproofing system to receive tile.
- * Waterproofing will be completed before shower tile installation.

5. Shower Wall Tile

- * Install tile on all designated shower walls over the Wedi waterproofing system.
- * Install tile around the shower perimeter as required.
- * Install four corner shelves within the shower.
- * Final tile layout, grout color, and material selections must be approved before installation.
- * Accent tile, decorative patterns, and a recessed niche are not included unless specifically added to the scope.

6. Bathroom Floor Tile

- * Remove existing bathroom flooring and prepare the subfloor for new tile.
- * The existing floor may contain two layers of flooring; removal of both layers is included where reasonably accessible and necessary for the new installation.
- * Inspect the exposed subfloor after flooring removal.
- * Install appropriate tile underlayment or substrate preparation as required by existing conditions.
- * Install new tile throughout the bathroom floor area.
- * Install grout and complete the tile installation.
- * Install a new transition between the bathroom flooring and adjoining hallway flooring.
- * If additional layers, adhesive, damaged subfloor, or concealed conditions require work beyond normal removal and preparation, the additional work will be addressed separately.

7. Hallway Flooring and Transition

- * Prepare the adjoining hallway area as necessary for the new bathroom flooring transition.
- * Install a new transition between the bathroom tile and hallway flooring.

- * If the hallway flooring requires additional repair, replacement, or leveling beyond the transition area, that work will be priced separately.

8. Drywall Repairs & Finishing

- * Inspect existing bathroom walls and ceiling after demolition.
- * Repair drywall affected by removal of the tub, shower, vanity, mirror, light, exhaust fan, plumbing, or water wall.
- * Install new drywall where required for the new water wall or plumbing relocation.
- * Patch, tape, mud, sand, and prepare repaired areas for primer and paint.
- * Existing walls and ceiling appear to be generally clean; full drywall replacement is not anticipated unless concealed damage is discovered.
- * Blend repaired areas as reasonably possible with the existing surrounding surfaces.

9. Vanity & Bathroom Accessories

- * Remove the existing vanity.
- * Install the new vanity or replacement vanity selected by the homeowner.
- * Install the vanity top.
- * Install the new mirror.
- * Install the new vanity light.
- * Install the new exhaust fan.
- * Install the toilet paper holder.
- * Install the towel bar or towel holder.
- * Install designated bathroom accessories in locations approved by the homeowner.
- * Connect the vanity plumbing to the existing or relocated water and drain lines as required.

10. Toilet

- * Remove the existing toilet as necessary during demolition and flooring installation.
- * Reinstall the existing toilet or install the replacement toilet selected by the homeowner.
- * Replace the toilet seal during reinstallation.
- * Connect the toilet to the existing plumbing.
- * Any required relocation or repair of the toilet drain or supply plumbing is excluded unless specifically added to the scope.

11. Baseboard & Trim

- * Remove existing baseboard and trim as required.
- * Install new baseboard throughout the renovated bathroom.
- * Install trim around affected areas as necessary.
- * Caulk, fill, and prepare new trim for painting.
- * Replace damaged or unusable trim discovered during demolition as required.

12. Painting

- * Prepare bathroom walls, ceiling, baseboard, and trim for painting.
- * Prime repaired drywall areas as required.
- * Paint bathroom walls.
- * Paint the ceiling.
- * Paint baseboard and trim.

- * Apply finish coats as necessary to achieve a consistent finished appearance.
- * Touch up areas affected by demolition, installation, and remodeling work.

ESTIMATED PRICING

The following is a preliminary contractor estimate for the described scope, assuming standard materials, normal access, generally clean existing walls and ceiling, and no major concealed damage:

- * Demolition, protection, and debris removal: \$1,500
- * Tub removal and shower-area preparation: \$1,500
- * New water wall and plumbing relocation allowance: \$1,800
- * Custom Wedi shower pan and waterproofing system: \$2,500
- * Shower wall tile installation, including four corner shelves: \$2,400
- * Bathroom floor demolition and tile installation: \$1,800
- * Hallway transition installation: \$300
- * Drywall repairs and finishing: \$900
- * Vanity, vanity top, mirror, light, exhaust fan, and accessory installation: \$1,500
- * Toilet removal and reinstallation: \$350
- * Baseboard and trim installation: \$600
- * Painting walls, ceiling, baseboard, and trim: \$1,200

Estimated labor and standard installation total: \$16,350

Recommended project price with normal material allowance: \$18,500–\$21,000

For a fixed quote based on the current described scope, the recommended project price is:

Kids Bathroom Tub-to-Shower Conversion and Full Remodel: \$19,500

This price assumes the homeowner supplies or approves standard-priced tile, vanity, vanity top, mirror, light, exhaust fan, toilet, accessories, paint, trim, and finish materials. Premium materials, shower door installation, recessed niche installation, permit fees, major plumbing repairs, structural repairs, subfloor replacement, and concealed damage are excluded unless added by written change order.

ITEMS TO BE DETERMINED

The following items will be finalized after demolition and homeowner selection:

- * Whether a new water wall is required on the left-hand side of the shower.
- * Final plumbing relocation requirements.
- * Final shower dimensions based on the space remaining after demolition.
- * Final custom Wedi pan dimensions.
- * Whether the existing floor contains two layers and the condition of the subfloor beneath them.
- * Final tile selections, layout, and grout color.
- * Final vanity, vanity top, mirror, light, exhaust fan, toilet, and accessory selections.
- * Any concealed plumbing, electrical, structural, framing, or subfloor conditions discovered during demolition.
- * Any additional work required due to unforeseen existing conditions.

EXCLUSIONS

- * Shower door or enclosure.
- * Accent or decorative tile.
- * Recessed shower niche unless specifically added to the scope.
- * Major structural modifications.
- * Repairs to concealed plumbing, electrical, framing, or subfloor damage not visible before demolition.
- * Plumbing relocation beyond the included allowance.
- * Replacement of hallway flooring beyond the bathroom transition area.
- * Permit fees or inspection fees unless specifically included.
- * Mold remediation, asbestos abatement, or hazardous-material removal.
- * Any work not specifically described in this proposal.

PROJECT NOTES & DISCLAIMERS

1. Existing Conditions: The scope is based on currently visible conditions. Hidden conditions cannot be fully determined until the existing tub, shower, flooring, vanity, and affected walls are opened.
2. Water Wall: A new water wall on the left-hand side will only be constructed if required to accommodate the plumbing or final shower configuration.
3. Plumbing: The price includes a plumbing relocation allowance based on the anticipated tub-to-shower conversion. Additional plumbing work beyond the allowance will be reviewed with the homeowner before proceeding.
4. Shower Size: The final shower size will be determined after demolition, plumbing inspection, and verification of the available space.
5. Wedi System: The shower will utilize a custom Wedi shower pan and Wedi waterproofing system. Installation will be completed according to the manufacturer's requirements.
6. Flooring Layers: The existing bathroom floor may contain two layers of flooring. Both layers will be removed where reasonably accessible and necessary. Additional charges may apply for unusually difficult removal, excessive adhesive, damaged subfloor, or required structural repairs.
7. Drywall: The existing walls and ceiling appear to be generally clean. Drywall work is expected to consist primarily of patches and repairs related to demolition and installation. Full replacement is not included unless required by concealed damage.
8. Tile: Tile is subject to normal variations in color, size, texture, and manufacturing. Final tile layout will be established before installation.
9. Existing Structure: Any structural, framing, subfloor, plumbing, electrical, or other concealed damage discovered during demolition is not included unless specifically added to the scope of work.
10. Change Orders: Additional work outside the stated scope will require homeowner approval before the work is performed.
11. Paint & Finish: Existing surfaces may show differences in texture or appearance after repairs due to age and existing conditions. Reasonable efforts will be made to provide a uniform finished appearance.
12. Schedule: Project duration may be affected by material availability, homeowner selections, concealed conditions, and unforeseen repairs discovered during demolition.

TOTAL PROJECT PRICE

Kids Bathroom Tub-to-Shower Conversion and Full Remodel: \$19,500

Additional Work / Change Orders: To be determined as required.

**Behind the scene material will range from 3000-4000 roughly. Please remember this is just a good guestimate and is only an educated range.
*Finish Material not priced in this quote

siding	\$0.00	1	\$0.00
Right side			
25 x 9			
- 1 soffit and fascia repair			
12' x 13'			
Soffit and fascia at the peak			
28' x 13'			
Fascia and soffit repairs			
Left side			
28' x 13'			
Repair at gable peak			
Back side			
50' x 9'			
Soffit of both ends of the back of the house			
Repair in middle from sagging. Repair entire soffit			

Shower Doors TBD	\$0.00	1	\$0.00
Shower Door Installation until final selections are made			

Subtotal	\$46,671.23
Total	\$46,671.23

****If paying with a credit card, there will be a 3.5% fee added to the invoice after we are notified that this is your choice of Payment.**

****Prices on material for future jobs may be subject to change depending on all new tariffs. If pricing is to change we will discuss prior to starting each project.**

****Only Scope of Work on this Contract is being Completed. If any additional work is required or requested, additional fees will apply and added to a Change-Order or the Final Invoice.**

****By you the Client Signing or E-Signing this Contract and agreeing to the terms of this scope listed makes this a Legal Binding Contract.**

****If for any reason the Contract needs to be Voided, a one-time fee of \$250 is to be paid for Cancellation of this Contract.**

****Final Payment is due on the day of Completion. Late Fees will apply.**

Attached is our Business Insurance

cid:EE7E8421-8B0D-4AB2-A39F-1F00598EB71D

By signing this document, the customer agrees to the services and conditions outlined in this document.

Joey Wykoff