

ESTIMATE



Prepared For

Chantelle Cunningham
994 Walnut Ct.
Mason, OH 45040
(513) 218-3631

Crystal Clear Cleaning & Contracting

7561 Easy St. , Unit D
Mason, OH 45040
Phone: (513) 614-8080
Email: crystalclearcontracting@yahoo.com
Web: crystalclearcontractors.com

Estimate # 4257
Date 08/28/2026

Description	Rate	Quantity	Total
Concrete Patio	\$7,450.62	1	\$7,450.62

Scope of Work – Stamped Concrete Patio & Grading

Contractor shall furnish all labor, equipment, and materials necessary to complete the following:

- * Fine grade and prepare subgrade for new concrete patio.
- * Install compacted stone base as required to provide a stable foundation.
- * Form and pour approximately 24' x 12' (288 sq. ft.) concrete patio.
- * Install reinforcing as required for residential applications.
- * Finish patio with an Ashlar Slate stamped pattern.
- * Integral color: Color TBD by Owner.
- * Apply release agent and sealer upon completion.
- * Saw-cut control joints as needed to help minimize random cracking.
- * Perform final grading around the patio to promote proper drainage away from the structure.
- * Clean work area and remove construction debris upon completion.

Exclusions & Disclaimers

- * Minor hairline cracking, color variations, and natural concrete imperfections are normal and are not considered defects.
- * Existing underground utilities, irrigation systems, drain lines, or unknown obstructions not identified prior to excavation are excluded. Additional charges will apply if encountered.
- * Unsuitable soils, excessive fill requirements, hidden debris, rock, or unstable subgrade requiring additional excavation or imported material will be billed as a change order.
- * Contractor is not responsible for damage caused by ground movement, settlement, freeze/thaw cycles, or acts of nature after completion.
- * Owner shall keep all foot traffic off the patio for a minimum of 48 hours and vehicle traffic

off the concrete for at least 7 days (28 days recommended for full cure

Includes all Labor
Includes all Material

No Permit Fees included for the Concrete Scope

Grade Yard	\$450.00	1	\$450.00
Grade Yard for New Concrete Patio			
Dump Fee	\$350.00	1	\$350.00
Deck Steps (Composite)	\$4,283.12	1	\$4,283.12
Deck Steps Installation			
Frame and Build Set of Steps			
Deck Steps			
Built out of Pressure Treated Wood for Framing			
Composite Decking:			
*Board Selection: Trex Naturals			
-Color: Coastal Bluff			
-Hidden Fasteners			
*No Railing Quoted			
One Set of Steps 5-6' Wide to the length of the door.			
Labor Only			
Includes all Material			
Gas Surcharge	\$200.00	1	\$200.00

Subtotal	\$12,733.74
Total	\$12,733.74

**If paying with a credit card, there will be a 3.5% fee added to the invoice after we are notified that this is your choice of Payment.

**Prices on material for future jobs may be subject to change depending on all new tariffs. If pricing is to change we will discuss prior to starting each project.

**Only Scope of Work on this Contract is being Completed. If any additional work is required or requested, additional fees will apply and added to a Change-Order or the Final Invoice.

**By you the Client Signing or E-Signing this Contract and agreeing to the terms of this scope listed makes this a Legal Binding Contract.

**If for any reason the Contract needs to be Voided, a one-time fee of \$250 is to be paid for Cancellation of this Contract.

**Final Payment is due on the day of Completion. Late Fees will apply.

Attached is our Business Insurance

cid:EE7E8421-8B0D-4AB2-A39F-1F00598EB71D

By signing this document, the customer agrees to the services and conditions outlined in this document.

Chantelle Cunningham