

ESTIMATE



Prepared For

Joe Gorley
3288 Woodlake Ct.
Loveland, OH 45140
(513) 502-4481

Crystal Clear Cleaning & Contracting

7561 Easy St. , Unit D
Mason, OH 45040
Phone: (513) 614-8080
Email: crystalclearcontracting@yahoo.com
Web: crystalclearcontractors.com

Estimate # 4266
Date 09/16/2026

Description	Rate	Quantity	Total
Lean To Roof Structure	\$26,691.14	1	\$26,691.14

Project Description

Contractor shall provide labor, materials, equipment, and installation necessary to construct a new roof structure over the existing composite deck, tie the new structure into the existing residence, complete the required exterior finishes, and restore all areas disturbed during construction.

1. Existing Deck Preparation

- Carefully remove approximately 6-8 feet of existing composite decking as necessary to provide access for excavation and installation of new structural footings.
- Protect existing deck structure and surrounding areas to the extent reasonably possible during construction.
- Upon completion of structural work and required inspections, reinstall the decking that was removed for access.
- Replace damaged decking or components caused by pre-existing conditions or material deterioration as a separate change order.

2. Footings, Posts & Structural Framing

- Excavate and install required concrete footings for the new roof structure.
- Install approximately two structural support posts located approximately 14 feet from the existing house, subject to final field measurements and structural requirements.
- Install required LVL beams and associated structural framing.
- Secure and support the new structure to the existing residence as required.
- Install ledger board and required structural connections.
- Contractor shall construct the structure in accordance with applicable building codes and

approved plans, where applicable.

3. Roof Structure & Roofing

- Construct roof structure approximately 16 feet wide, based upon field conditions and final measurements.
- Install required roof framing and sheathing.
- Install metal roofing system.
- Properly flash the roof-to-house connection.
- Install required flashing around ledger, siding, roof intersections, and other areas necessary to provide a weather-resistant installation.
- Tie the new roof structure into the existing house while making reasonable adjustments to existing siding as required.

4. Exterior Trim, Soffit & Fascia

- Install PVC trim on exposed posts, beams, and other designated exterior structural components.
- Complete soffit and fascia installation.
- Install required exterior flashing.
- Make necessary siding adjustments around the new ledger, roof connection, and structural components.
- Correct and reinstall affected siding located underneath and below the ledger board.
- Finished trim shall be painted or stained at the Owner's selection, subject to the suitability of the selected finish for the materials installed.

5. Gutters & Downspouts

- Install approximately 6-inch gutters along the new roof structure.
- Install required downspouts and direct water away from the structure and foundation.
- Final downspout discharge locations shall be based upon existing site conditions and reasonable drainage requirements.

6. Beadboard Ceiling

- Install exterior beadboard to the underside of the new roof structure.
- Properly fasten and finish beadboard installation.
- Stain or paint beadboard based upon Owner's selected finish.
- Color and finish selection must be provided in a timely manner to prevent project delays.

7. Electrical

- Provide electrical wiring necessary for one ceiling fan location.
- Install required electrical components within the scope of the existing electrical system and applicable code requirements.
- Final ceiling fan fixture shall be supplied by Owner unless specifically included elsewhere in the contract.
- Any electrical upgrades, new circuits, panel modifications, underground work, or unforeseen electrical repairs are excluded unless specifically stated and will be handled by change order.

8. Screenshot Installation (One Side Only)

- Construct one privacy wall along the designated side of the Screeneze System.
- Contractor will obtain material.
- If any adjustments to the existing structure are needed for a proper installation additional fees may apply.
- Exact privacy wall dimensions and configuration shall be based upon field conditions and final layout.

9. Final Restoration & Cleaning

- After all structural work has passed required final inspections, reinstall the existing composite decking removed for access.
- Complete all remaining trim, flashing, siding, soffit, fascia, beadboard, and finish work included within this scope.
- Paint or stain finished surfaces as selected by Owner.
- Pressure wash the existing deck and affected exterior deck areas upon completion.
- Remove normal construction debris generated by Contractor's work.

CONTRACTOR PROTECTION & GENERAL CONDITIONS

Existing Conditions

Contract price is based upon visible and reasonably accessible existing conditions at the time of estimating. Contractor is not responsible for concealed, defective, deteriorated, improperly constructed, or code-deficient conditions that are discovered after work begins.

Any such conditions, including but not limited to deteriorated framing, inadequate existing footings, damaged siding, hidden water damage, structural deficiencies, electrical deficiencies, plumbing issues, or unsuitable attachment points, shall be treated as additional work and completed only upon Owner authorization through a change order.

Structural & Existing House Conditions

Contractor will make reasonable efforts to properly connect the new structure to the existing residence. Contractor is not responsible for hidden conditions within the existing walls, framing, foundation, roof, siding, or other concealed areas.

If existing construction does not provide adequate structural support for the proposed connection, additional structural work may be required and will be quoted separately.

Materials & Product Availability

Where an exact existing material, color, profile, texture, or manufacturer is no longer available, Contractor shall make reasonable efforts to provide the closest commercially available match. Exact matching of existing materials cannot be guaranteed.

Change Orders

Any work outside the scope described above must be approved by the Owner before the additional work is performed, except for emergency work reasonably necessary to protect the property from immediate damage.

Additional work may include additional labor, materials, equipment, permits, engineering, inspections, or subcontractor costs.

Permits & Inspections

Required permits and inspections shall be handled as agreed upon in the contract. Contractor is responsible for performing contracted work in accordance with applicable code requirements.

Contractor is not responsible for delays caused by building departments, inspectors, engineering requirements, material availability, weather, utility companies, or other circumstances outside Contractor's reasonable control.

Weather & Scheduling

Exterior construction is subject to weather and site conditions. Rain, excessive moisture, extreme temperatures, high winds, material delays, inspections, or other conditions outside Contractor's control may affect the project schedule.

Such delays shall not constitute a breach of contract or grounds for withholding payment.

Existing Deck & Property

Contractor will use reasonable care when removing and reinstalling the existing decking. Existing materials may contain hidden damage, deterioration, previous improper installation, or normal wear.

Contractor is not responsible for failure of existing materials that are damaged or deteriorated due to age, prior installation, weather exposure, or conditions unrelated to Contractor's work.

Owner-Supplied Materials

Any Owner-supplied materials must be delivered to the jobsite in a timely manner and must be suitable for installation. Contractor is not responsible for defects, shortages, incorrect quantities, incorrect colors, or incompatibility of Owner-supplied materials.

Delays caused by Owner-supplied materials may extend the project schedule.

Finish Selection

Owner shall select all paint, stain, beadboard finish, decking/privacy-wall material, and other finish colors in a timely manner.

Minor variations in color, texture, grain, sheen, and appearance are normal and shall not be considered defects, particularly when attempting to match existing materials.

Water & Weather Resistance

Contractor will install flashing, roofing, gutters, and related components in accordance with standard construction practices and applicable manufacturer requirements. Contractor does not warrant that existing portions of the residence are free from leaks or that pre-existing water

intrusion will be eliminated.

Any pre-existing water damage or concealed moisture-related conditions discovered during construction are excluded unless specifically included by written change order.

Final Payment

Final payment shall become due upon substantial completion of the contracted work, subject to completion of agreed-upon punch-list items.

Minor cosmetic items, material backorders, weather-related touch-ups, or items outside Contractor’s control shall not constitute grounds for withholding the entire remaining contract balance.

Protection of Contractor’s Work

Contractor is not responsible for damage to completed work caused by other contractors, subcontractors, homeowners, guests, pets, landscaping companies, utility companies, weather events, or other parties after the work has been completed.

Warranty

Contractor warrants workmanship for the period of 1 year from project completion. Manufacturer warranties on roofing, decking, gutters, electrical components, paint, stain, PVC, and other manufactured products shall remain subject to the individual manufacturer’s warranty terms.

Contractor shall not be responsible for failures caused by misuse, lack of maintenance, alterations by others, normal wear and tear, severe weather, acts of nature, or pre-existing conditions.

Final Acceptance

Upon completion, Owner shall have a reasonable opportunity to inspect the work and identify legitimate punch-list items within the contracted scope. Completion of minor punch-list items shall not delay payment for completed portions of the project.

By approving the scope of work, Owner acknowledges that construction involves existing conditions and that exact matches to existing materials, finishes, colors, and textures cannot always be guaranteed.

All work not specifically listed in this Scope of Work is excluded and shall require a written change order before proceeding.

- Includes all Labor
- Includes all Material
- *Client to provide ceiling fan

Permit Fees	\$0.00	1	\$0.00
This is the fee that the County/City/Township charge to do the permit. Each County/City differs. This will be added to the final Invoice			

Permit Processing Fee	\$500.00	1	\$500.00
Costs for Drawing Sketch			
Costs for Applying for Permit			
Costs for Gas			
Costs for Time Dealing with Inspectors and Inspections			

Labor Only

Subtotal	\$27,191.14
Total	\$27,191.14

**If paying with a credit card, there will be a 3.5% fee added to the invoice after we are notified that this is your choice of Payment.

**Prices on material for future jobs may be subject to change depending on all new tariffs. If pricing is to change we will discuss prior to starting each project.

**Only Scope of Work on this Contract is being Completed. If any additional work is required or requested, additional fees will apply and added to a Change-Order or the Final Invoice.

**By you the Client Signing or E-Signing this Contract and agreeing to the terms of this scope listed makes this a Legal Binding Contract.

**If for any reason the Contract needs to be Voided, a one-time fee of \$250 is to be paid for Cancellation of this Contract.

**Final Payment is due on the day of Completion. Late Fees will apply.

Attached is our Business Insurance

cid:EE7E8421-8B0D-4AB2-A39F-1F00598EB71D

By signing this document, the customer agrees to the services and conditions outlined in this document.

Joe Gorley